



TEST REPORT

**Name of Product: Three Phase Pad Mount
Transformer**

Type of Product: ZGS-H-300

Ex-work Serial No: JM2210015

Test Place: META POWER SOLUTIONS

Testing Date: December 27, 2022

1、 Specification									
Rated Capacity (KVA)	300	Product Type	ZGS-H-300		60HZ	Factory Serial No.	JM2210015		
3Voltage Combination	HV(kV)	23	Current	HV (A)	7.53	Angular displacement	YNyn		
	LV(kV)	0.6		LV(A)	288.68				
2、 Measurement of voltage ratio									
Tapping Position	HV and LVThe Voltage Value of the Test	HV (V)	LV (V)	HV/LV (%)					
				AB/ab		BC/bc		AC/ca	
A	The Grade and Accuracy:QJ3 5A Grade 0.2	24150	600	0.01		0.01		0.01	
B		0.01		0.02		0.01			
C		0.02		0.02		0.02			
D		0.02		0.02		0.03			
E		0.03		0.03		0.03			
3、 Measurement of winding resistance (Routine)									
Tapping Position	Winding Resistance Measurement	HV(Ω)						LV(Ω)	
		0A	0B	0C	AB	BC	CA	oa	0.003103
4.639		4.655	4.649	9.278	9.287	9.260	ob	0.003079	
4.515		4.530	4.525	9.025	9.044	9.030	oc	0.003064	
4.391		4.404	4.399	8.776	8.781	8.761	ab	0.005955	
4.267		4.279	4.276	8.527	8.532	8.520	bc	0.005941	
4.143		4.155	4.152	8.283	8.283	8.280	ca	0.005971	
The Meter NO. and Grade of Accuracy		HCR3102A Grade 0.2	Temperature		20 ℃		Humidity		100%
4、 No-load loss and no-load current test.									
Test Items		No-Load Loss at 100% rated voltage W				No-Load Current %			
Measured Value		344				0.11			
5、 Load loss and Short circuit test.									
Test Items	Load Loss at 75℃ and rated voltage W			Total Loss W		Short Circuit Impedance at 75℃			
Measured Value	1988			2332		3.87			

6、 Applied voltage test				
Power Frequency withstand Voltage Test				
Test Time	60 S			
The Test Voltage(kV)	HV 55 /LV5			
7、 Induced Over Voltage Withstand Test				
Induced Over Voltage Withstand Test(kV)	1.2 (rms) for L.V. bushing			
8、 Insulation Resistance test				
location	Insulation Resistance(M Ω) at 20℃ R60			
HV-LV	>2500			
HV-E	>2500			
LV-E	>2500			
9、 Other Information.				
The Active Part's Weight of Lifting	The Weight of Insulation Oil	Total Weight	The Temperature Rise of the Oil	Oil Pressure
888kg	912L	2500kg	<65K	45KV
10、 Leakage test （Routine）				
Test method	Applied pressure （kPa）	Duration(h)	Residual pressure （kPa）	Result
The static pressure method	20	12	18	No leakage and no damage
11、 Outer inspection				
The nameplate, sign, earthing terminal, mark of terminal meets the requirement. There is no evidence of leakage.				
Test Date: December 27, 2022				

Transformer Test Report

Certificate of Compliance for Three-Phase Transformer

According to IEEE Std C57. 12.34-2021

This inspection and testing of this product are complying

with the

factory technical conditions and allowed leave the

factory.

Certificating

Quality Assurance Department

META POWERSOLUTIONS